





Before Leaving Campsite Exterior												
												Turn off all lights (inside and out).
												Turn off A/C / Heat
												Turn the switch on the water heater off.
												Turn the Hot Water switch inside the camper off.
												Turn inside breakers off.
												Turn shore power breaker off.
												Unplug power cable from trailer.
												Unplug power cable from shore power.
												Disconnect water hoses.
												Put water filter in refrigerator.
												Open sink and shower valves and let the water out.
												Check the refrigerator is latched correctly.
												Verify refrigerator switches to gas.
												Verify all items inside are secure.
												Clean / Clear slide areas outside (3).
												Clear slide areas inside (3).
												Close slides (3).
												Verify steps are up.
												Verify handrail is in.
												Verify door is locked.
Dump Station												
												Connect drain hose to the ground.
												Connect hose to the gray/black water tank.
												Open black water valve.
												Attach blue water hose to flush connector.
												Run flush for about 30 minutes.
												Turn off flush water.
												Close black water valve.
												Open gray water tank valve 1.
												Store blue water hose.
												Close gray water valve 1.
												Open gray water tank valve 2.
												Close gray water valve 2.
												Store drain hose.